CHITALDRUG DIVISION.

Dated 4ht March 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 24th March 1930, for the reconstructing the Mosque at Harihar. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 30th August 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chitaldrug, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Reconstructing the Mosque at Harihar" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer Chitaldrug Division who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

Abstract for reconstructing the Mosque at Harihar.

No.	Items of work	Unit	Quantity
1	Dismantling the existing dilapidated Mazid and removing the debries.	Lump sum	
2	Earthwork excavation and filling in basement ...	C.yds.	91
3	Concrete in chunam	C.ft.	1,742
4	Trap stone in chunam	,,	2,200
5	Burnt brick in chunam	,,	1,619
6	Burnt stone slabs 6" thick dressed and fixed	S.ft.	184
	Do 8" do	,,	90
7	Plastering with chunam	Sqr.	28·04
8	Teakwood door paunelled shutters including chocolate painting, etc, complete.	S.ft.	28
9	Teakwood windows with pannelled shutters 4" iron bars, hinges, hooks painting, etc., complete.	,,	108
10	Teakwood work wrought and put up with wood oiling ...	C.ft.	58·98
11	Roofing with pucca terrace 9"	Sqr.	5·08
12	Roofing with 1st Class Mangalore tiles on teak rafters, etc., complete.	,,	2·26
13	Flooring with Cuddapha slabs (1½" to 2") on 6" concrete bed with cement pointing.	,,	4·19
14	A Rolled steel beams and joists including hoisting ...	Cwt.	12.5
15	Burnt brick in chunam parapet ornamental with pillasters	R.ft.	100
16	White washing two coats	Sqr.	11·50
17	Colour washing	,,	11·68
18	Constructing masonry pillars with stone base and capital, etc., complete.	No.	3
19	Cornice 9" to 12"	R.ft.	102
20	Teakwood ornamental eave board with fixing	,,	28
21	Constructing dome over sacred portion complete ...	Lump sum	
22	Thick mortar bonds at ends of roof	R.ft.	24
23	Thin do	,,	28
24	Masonry finials ornamental complete	No.	10
25	Clearing site and levelling ground and pointing to basement	Lump sum	

A. TIMMOJI RAO,